



Cuttack Central Co-operative Bank Ltd.

Head Office, Nimchouri, Cuttack – 753002

website – www.cuttackccb.co.in

No. 5804

Dt. 23.03.2022

SHORT TENDER CALL NOTICE

Sealed tenders are invited from registered and eligible Civil Contractors/ Experienced Firms for construction of Toilet block in first floor and renovation of one room in Cuttack Central Cooperative Bank Ltd. Head Office on behalf of Chief Executive Officer, Cuttack Central Coop. Bank Ltd. Nimchouri, Cuttack-753002 as follows.

Sl No	Name of the work	Estimated Tender amount excluding GST	EMD Amount (Rs)	Eligibility class of Contractor.	Period of completion.
1	Construction of Toilet block in first floor and renovation of one room.	191193.00	1900.00	'D' Class & above or Experienced Contractor with similar kind of work.	45 days

Terms and Conditions

1. The tender document will be available in Bank website- www.cuttackccb.co.in from 25.03.2022.
2. Bid shall contain copy of valid license, PAN Card, GST Certificate, IT Return of last three financial year 2018-19, 2019-20 and 2020-21.
3. Price Bid shall contain the filled up tender form in proper manner accompanied by EMD.
4. The sealed envelope shall be put in a sealed cover supercribed with Tender for "Construction of Toilet block in first floor and renovation of one room of Cuttack CCB" and submitted in Head Office of the Bank at Nimchouri, Cuttack-753002.
5. The tender papers will be submitted at Head Office from dt. 25.03.2022 to 31.03.2022 upto 4.00 PM with DD for Rs. 1900=00 in favour of CEO, Cuttack Central Coop. Bank Ltd payable at Cuttack and will be opened on dt. 05.04.2022 at 4.00 PM in presence of Tenderer or their authorized representative at Cuttack CCB Head Office, Nimchouri, Cuttack-753002.
6. The EMD shall be deposited in form of crossed Account Payee Demand Draft/Bankers Cheque from a Nationalized Bank/Scheduled Bank in favour of Chief Executive Officer, Cuttack Central Coop. Bank payable at Cuttack. Tender deposited without earnest money in proper form shall be rejected without assigning any reason thereof.
7. Authority is not bound to accept the lowest tender and reserves the right to cancel or reject any or all tenders without assigning any reason thereof.

Chief Executive Officer

Memo No. 5805/Dt. 23.03.2022

1. Copy to Notice Board of Cuttack CCB Head Office
2. Copy to all Branches for publish in the Notice Board

Chief Executive Officer

Name of work :- Construction of Toilet block in First Floor and Renovation of one Room in Cuttack Central Co - operative Bank Ltd., Nimchouri, Cuttack - 753 002

Sl. No.	Description	Qty.	Unit	Rate	Amount
1.	Cutting of vegetation growth in backside all Labour T & P etc. complete. Helper 4 number x 6 days	24	Nos.		
2.	16 mm thick cement plaster (1:6) inside wall surface Including watering curing etc. complete.	41.15	Sqm		
3.	12 mm thick cement plaster (1:3) ceiling Plaster including watering curing etc.	8.31	Sqm		
4.	Flyash brick masonry in C.M (1:4) super structure using flyash Bricks of size (25cm x 12cm x 8cm) including Watering curing etc complete				
	(i) Ground Floor	6.68	Cum		
	(ii) First floor (Toilet Block)	5.77	Cum		
5.	Cement concrete prop (1:3:6) using 4 cm size BHCB granite stone mental including watering Curing etc. complete. (Ground Floor)	0.83	Cum		
6.	Cement concrete prop (1:1.5:3) using 12 mm Size BHCB granite stone mental including Watering curing etc. complete. (Ground Floor).	0.63	Cum		
7.	R.C.C.M.20 using 12mm to 20 mm size hard granite stone chips with centring and shuttering including watering curing etc. complete.				
	(i) First floor (Toilet Block)	0.50	Cum		
	(ii) RCC Beam (Second Floor)	0.44	Cum		
	(iii) Rcc roof slab (Second Floor)	0.84	Cum		
8.	Cutting bending and binding and tying with M.S road or tor steel all cost materials labour T&P etc. complete.				
	(i) First floor (Toilet Block) Lintal	0.50	Qntl.		
	(ii) Second floor Beam & Roof Slab	1.72	Qntl.		
9.	Supplying G.I PIPE of approved quality and size All cost materials labour T&P etc. complete.				
	(a) 50 mm dia G.I pipe (Heavy)	18.28	Rmt		
	(b) 40 mm dia G.I pipe (heavy)	21.94	Rmt		
	(c) 25 mm x 5mm MS flat	7.30	Kg		
10.	Labour for fitting and fixing of fabrication work With welding charges all labour T&P etc. complete.				
	(a) 50 mm Dia G.I pipe (heavy)	142.58	Kg		
	(b) 40 mm Dia G.I pipe (heavy)	121.50	Kg		
	(c) 25 mm x 5mm MS flat	7.30	Kg		



11.	Providing fitting & fixing of aluminium coated Of TATA BRAND 0.47 mm thick G.C.I sheet roofing all cost of materials labour T&P etc.	24.52	Sqm		
12.	Supplying fitting & fixing of 150 mm dia P.V.C down rain water pipe all cost of materials Labour T&P etc. complete.	5.48	Rmt.		
13.	12 mm thick cement plaster (1:6) outside Surface including watering curing etc.				
	(i) Ground Floor	10.34	Sqm		
	(ii) First Floor	10.34	Sqm		
14.	Painting two coats with weather seal coat a over a coat of water bound wall primer all cost materials labour etc. complete.				
	(i) Ground Floor	10.34	Sqm		
	(ii) First Floor	33.28	Sqm		
15.	Providing laying vinyl flooring (I.S.I) PVC (M.F) supper roll 2.00mm thick. All cost materials labour etc complete.	8.31	Sqm		
16.	Distempering two cots over a coat of Primer of approved quality all cost of Materials labour T&P etc. complete.	49.47	Sqm.		
17.	Clearance of debris by mechanical means Loading un loading charges away from 5 km Distance all labour T&P etc. complete.	29.40	Cum		
	Total :				

