



Cuttack Central Co-operative Bank Ltd.
Head Office, Nimchouri, Cuttack – 753002

website - www.cuttackccb.co.in

No. 5913

Dt. 06.03.2023


SHORT TENDER CALL NOTICE

Sealed tenders are invited from registered and eligible Civil Contractors/ Experienced Firms for construction of boundary wall of Cuttack Central Cooperative Bank Ltd. Erasama Branch on behalf of Chief Executive Officer, Cuttack Central Coop. Bank Ltd. Nimchouri, Cuttack-753002 as follows.

SI No	Name of the work	Estimated Tender amount excluding GST	EMD Amount (Rs)	Eligibility class of Contractor	Period of completion
1	Proposed construction of boundary wall in Erasama Branch	Rs.7,86,000.00	Rs.7,800.00	'D' Class & above or Experienced Contractor with similar kind of work	60 days

Terms and Conditions

1. The tender document will be available in the Bank website-www.cuttackccb.co.in from dt 06.03.2023 to 18.03.2023.
2. Bid shall contain copy of valid license, PAN Card, GST Certificate, IT Return of last two financial year 2020-21 and 2021-22.
3. Price Bid shall contain the filled up tender form in proper manner accompanied by EMD.
4. The sealed envelope shall be put in a sealed cover super scribed with Tender for "construction of boundary wall of Erasama Branch and submit in Head Office of the Bank at Nimchouri, Cuttack-753002.
5. The tender papers will be submitted at Head Office from dt.06.03.2023 to 18.03.2023 upto 3.00 PM along with DD for Rs.7800.00 in favour of CEO, Cuttack Central Coop. Bank Ltd payable at Cuttack. It will be opened on dt.18.03.2023 at 4.00 PM in presence of Tenderer or their authorized representative at Cuttack CCB Head Office, Nimchouri, Cuttack-753002
6. The EMD shall be deposited in form of crossed Account Payee Demand Draft/Bankers Cheque from a Nationalized Bank/Scheduled Bank in favour of Chief Executive Officer, Cuttack Central Coop. Bank payable at Cuttack. Tender deposited without earnest money in proper form shall be rejected without assigning any reason thereof.
7. 5% of the final bill will be kept as Security Deposit, which will be released after six months of the completion of work.
8. Authority is not bound to accept the lowest tender and reserves the right to cancel or reject any or all tenders without assigning any reason thereof.


Chief Executive Officer

Memo No. 5914(39)/Dt. 06.03.2023

1. Copy to Notice Board of Cuttack CCB Head Office
2. Copy to all Branches for publish in their Notice Board


Chief Executive Officer

ESTIMATE

Construction of Boundary wall of Erasama Branch of Cuttack Central Coop.Bank

Sl.No.	Description	Quantity	Rate	Amount
1	Earthwork in excavation for foundation in hard soil within intial lead of 50m 7 intial Lift of 1.50m including dressing & leveling the bed etc complete.Boudnary wall	7.20		
2	Labour & materials for filling foundation & plinth with river sand watering ramming etc. complete including cost of all labour material etc complete including 1% cess, Boundary wall	3.60		
3	Reinforced/plain cement concrete M 15 grade with 20mm and down coarse Aggregates boundary wall	1.80		
4	single under reamed piler foundation with RCC M20 using 20mm size black hard granite CB chips Total nos of plles	30.00		
5	Reinforce/plain cement concrete M20 grade with 20mm and down coarse aggregates column plinth beam Coplmg	3.75 5.00 1.50 <hr/> 10.25		
6	Brick work in fly ash brick in cement mortal (1:6) in sub structure including cost of all labour material cost complete including 1% cess boundary wall Ist Footing	2.27		
7	Brick work in fly ash brick in cement Mortal (1:6) in sup structure cost of all labour material etc complete. including 1% cess Boundary wall in sup.structure	36.25		
8	Form work F1 finish for concrete in canal structures column Beam	60.00 40.00 <hr/> 100.00		

Handwritten signature



9	Labour for cutting bending binding & stretching of MS road including all cost including 1% cess i.Column main bar ii.8mm ring in column iii.12mm for bar in plinth iv.Bmm for bar ring in	13.844		
10	Providing MS grill Door including cost conveyance royalties of all including 1% cess Painting two coat with any approved shads over a coat of primer including cost conveyance & all labour materials etc complete including 1% cess	12.00		
11	16mm thick c.p using cm (1:6) Brick including all charges including cost of all labour materials etc complete including 1% cess Boundary wall	380.00		
12	Wheather coat paint of 2 coats to outside wall with any approved shade over a coat of priming with any approved Qnty as epr item No.7	380.00		

Amal

